


COLLECTOR (AT INTERSECTIONS)



COLLECTOR (MID BLOCK)

NOTES:

- 1. SLOPE PAVEMENT 2% FROM CROWN TO LIP OF GUTTER.
- 2. TYPICAL SECTIONS SHOW MINIMUM REQUIREMENTS. ADDITIONAL ROADWAY WIDTHS AND RIGHT OF WAY MAY BE REQUIRED TO ACCOMMODATE TRAFFIC OR OTHER DEVELOPMENT NEEDS SUCH AS TURN LANES, ACCEL/DECEL LANES, EXTRA LANES, PEDESTRIAN OR BICYCLE FACILITIES, LANDSCAPING, UTILITIES OR CONSTRUCTION REQUIREMENTS.
- 3. WHEN FLOWLINE ELEVATIONS ARE NOT EQUAL, PAVEMENT SHALL BE SLOPED 2% FROM THE HIGHER GUTTER LIP. THE MAXIMUM STREET CROSS SLOPE IS 4%.
- 4. ATTACHED SIDEWALKS/BIKEPATHS ON COLLECTOR ROADWAYS ARE NOT ALLOWED.
- 5. DRIVEWAY ACCESS IS NOT ALLOWED ON COLLECTOR ROADWAYS.
- 6. CERTAIN TREES ARE NOT ALLOWED IN TREE LAWNS. PLEASE CONTACT THE TOWN OF FREDERICK PLANNING DEPARTMENT.
- 7. TREES MAY NOT BE LOCATED WITHIN 30' OF A TRAFFIC SIGN IN THE DIRECTION OF TRAVEL ONLY.
- 8. TREES MAY NOT BE LOCATED WITHIN 100' OF A TRAFFIC SIGNAL IN THE DIRECTION OF TRAVEL ONLY.
- 9. THE APPROVED TRAFFIC STUDY WILL DETERMINE THE STORAGE AND TAPER LENGTHS FOR TURN LANES AT INTERSECTIONS.
- 10. SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2%.

TYPICAL COLLECTOR STREET CROSS-SECTIONS

NTS

