



CONCRETE CURB EDGING, OR SIDEWALK. HOLD GRADE 1" BELOW EDGE. PRUNE ALL DAMAGED OR DEAD WOOD AFTER PLANTING AND MULCHING.

SET SHRUB AT THE GRADE AT WHICH IT GREW IN THE CONTAINER OR OR NURSERY. ALL JUNIPER PLANTS SHOULD BE PLANTED SO TOP OF ROOT MASS OCCURS AT FINISHED GRADE OF MULCH LAYER

APPLY SPECIFIED MULCH AT 4" DEPTH.

FINISHED GRADE

FILL PLANT PIT WITH SPECIFIED BACKFILL MIXTURE. SEE SPECIFICATIONS IN SECTION 1500 FOR COMPOSITION.

CONTAINER SHRUBS: REMOVE CONTAINER. PLACE ROOTBALL ON UNDISTURBED SOIL. SCORE CONTAINER ROOTBALLS WITH ENCRICLING ROOTS.

BALLED AND BURLAPPED SHRUBS: COMPLETELY REMOVE METAL BASKET. REMOVE TOP 1/3 OF TWINE AND TOP 1/3 OF BURLAP.

NOTES

1. HOLD MULCH GRADE 1" BELOW EDGE OF SIDEWALK, EDGING, OR CURB.
2. DO NOT PLANT ANY PLANT WITH A ROOTBALL THAT IS NOT IN COMPLIANCE WITH THE COLORADO NURSERY ACT REQUIREMENTS.

SHRUB PLANTING

NTS



TOWN OF FREDERICK
STANDARDS & SPECIFICATIONS

1500-06